



Dublin San Ramon Services District

Final Report

Wastewater Collection System Master Plan Update

June 2005



Acknowledgements

Dublin San Ramon Services District

David Requa, District Engineer

David Behrens, Principal Engineer

Stanley Kolodzie, Associate Engineer (Project Manager)

Rhodora Biagtan, Associate Engineer

Steve Delight, Assistant Engineer

Robert Anderson, Field Operations Supervisor

Darin Winton, Wastewater Systems Operator

John Archer, Financial Services Supervisor

Aaron Johnson, Engineering Technician

MWH Americas, Inc.

Gisa Ju, Project Manager

Nelson Schlater

Vivian Cho

Craig Smith

Roberts McMullin

Simon Heart

Paul Giguere, Technical Review

John Bergen, Technical Review

E2 Consulting Engineers, Flow Monitoring

Table of Contents

EXECUTIVE SUMMARY

Background and Master Plan Objectives.....	ES-1
DSRSD Wastewater Service Area and Collection System.....	ES-1
Land Use Projections and Design Flows	ES-2
Hydraulic Modeling and Capacity Analysis.....	ES-2
Recommended Capital Improvement Projects.....	ES-4
Implementation Recommendations	ES-5
Other Recommendations.....	ES-6

SECTION 1 – INTRODUCTION

Background and Master Plan Objectives.....	1-1
DSRSD Wastewater Service Area.....	1-1
DSRSD Wastewater Collection System	1-2
Scope of Master Plan Update.....	1-2
Report Organization.....	1-5

SECTION 2 – LAND USE PROJECTIONS AND DESIGN FLOWS

Land Use Projections	2-1
Wastewater Flow Components	2-2
Development of Design Wastewater Flows.....	2-4
Base Wastewater Flow.....	2-4
Groundwater Infiltration.....	2-11
Rainfall-Dependent I/I	2-12
Design Flow Condition.....	2-15
Wastewater Flow Projections	2-18
Comparison to Previous Flow Projections.....	2-18
Potential Impact of Water Conservation.....	2-20
Future Connections	2-20

SECTION 3 – MODELING AND CAPACITY ANALYSIS

Model Development.....	3-1
Model Network Data.....	3-1
Model Loading Data	3-2
Model Calibration	3-3
Design Flow Scenarios	3-3
Boundary Conditions	3-3
Capacity Analysis Results	3-4
Preliminary Solutions for Capacity Deficiencies.....	3-8

SECTION 4 - SEWER IMPROVEMENT PROJECTS

Capacity Relief Projects..... 4-1

 Construction Considerations..... 4-1

 Project 1 - Dublin Boulevard West Relief Sewer 4-3

 Project 2 - Dublin Boulevard East Relief Sewer 4-4

 Project 3 - Dublin Boulevard Lift Station Expansion..... 4-5

 Project 4 - Donahue Drive/Vomac Road Relief Sewer 4-5

 Project 6 - Dublin Trunk Relief Sewer 4-6

Trunk Sewer Extensions 4-6

 Project 7 - Easter Dublin Trunk Sewer Extension..... 4-7

Other Sewer Improvement Projects..... 4-7

 Project 8 - Alamo Creek/I-580 Crossing Sewer Replacement..... 4-7

 Project 9 - OSH Sewer Replacement..... 4-8

 Parks RFTA Sewer Improvements 4-8

SECTION 5 – RECOMMENDED CAPITAL IMPROVEMENT PROGRAM

Capital Improvement Projects and Costs..... 5-1

Allocation of Project Costs 5-1

Project Priorities and Schedule 5-4

Implementation Recommendations 5-5

SECTION 6 – OTHER RECOMMENDATIONS

Regulatory Requirements..... 6-1

Operation and Maintenance Criteria Review..... 6-2

 Current Practices..... 6-2

 Potential Enhancements to Current Practices 6-3

Renewal/Replacement Criteria Review 6-5

 Collection System Inventory 6-5

 Methods Used to Project Renewal/Replacement Needs..... 6-5

 Potential Enhancements to Current Practices 6-6

APPENDICES

- Appendix A - Model Results
- Appendix B - Project Descriptions and Cost Estimates

TECHNICAL MEMORANDA
(bound separately and contained on CD at back of report)

Appendix C - TM 1 - Hydraulic Model Evaluation

Appendix D - TM 2 - Land Use Planning Criteria

Appendix E - TM 3 - Design Flow and Hydraulic Criteria

Appendix F - TM 4 - Wastewater Flow Projections

Appendix G - TM 5 – Hydraulic Model Results

Appendix H - TM 6 – Sewer Improvement Projects

Appendix I - TM 7 – Capital Improvement Program

Appendix J - TM 8 – Review of O&M and System Replacement Criteria

LIST OF TABLES

Table No.	Title	Page
1	DSRSD Wastewater Collection System Master Plan Design Flow Criteria	ES-3
2	Estimated Flows and Equivalent Connections in DSRSD Local Sewer Service Area.....	ES-3
3	Wastewater Flow Projections	ES-4
4	Estimated Sewer Improvement Project Costs.....	ES-4
5	Proposed Schedule for Collection System Capital Improvement Projects.....	ES-5
1-1	DSRSD Sewer Inventory	1-2
2-1	Consolidated Land Use Categories and Densities	2-2
2-2	Base Wastewater Flow Unit Factors.....	2-5
2-3	Projected Base Wastewater Flows by Sewer Subbasin	2-7
2-4	Groundwater Infiltration Rates	2-12
2-5	Rainfall-Dependent I/I Hydrograph Parameters	2-14
2-6	Design Storm Rainfall for DSRSD	2-16
2-7	Wastewater Flow Projections	2-18
2-8	Comparison of Buildout Wastewater Flow Projections: 2000 vs. 2005 Master Plans.....	2-19
2-9	Comparison of Buildout Wastewater Flows With and Without Water Conservation	2-21
2-10	Estimated Flows and Equivalent Connections in DSRSD Local Sewer Service Area.....	2-21
3-1	Sewer Subbasin Numbering Convention.....	3-2
3-2	Predicted Trunk System Capacity Deficiencies.....	3-5
3-3	Pipe Segments with Flat or Negative Slope.....	3-6
4-1	Proposed Sewer Improvement Projects	4-2
5-1	Estimated Sewer Improvement Project Costs.....	5-2
5-2	Allocation of Project Costs	5-2
5-3	Proposed Schedule for Collection System Capital Improvement Projects.....	5-4

LIST OF FIGURES

Figure No.	Title	Page or Following Page
1	Study Area Boundary.....	ES-1
2	Predicted Capacity Deficiencies Under Future PWWF.....	ES-4
3	Proposed Sewer Improvement Projects.....	ES-4
1-1	Study Area Boundary.....	1-1
1-2	Wastewater Collection System.....	1-2
2-1	Planned Land Uses.....	2-1
2-2	Wastewater Hydrograph Components.....	2-3
2-3	Flow Monitor Locations and Meter Areas.....	2-4
2-4	Sewer Subbasins.....	2-4
2-5	Design Diurnal Curves.....	2-10
2-6	Synthetic RDI/I Hydrograph Components.....	2-13
2-7	Design Storm for DSRSD Collection System Master Plan.....	2-17
3-1	Modeled Trunk Sewer System.....	3-1
3-2	Predicted Capacity Deficiencies Under Existing PWWF.....	3-4
3-3	Predicted Capacity Deficiencies Under Future PWWF.....	3-4
3-4	Dublin Boulevard West Sewer – Hydraulic Gradeline at Future PWWF.....	3-7
3-5	Dublin Boulevard East Sewer – Hydraulic Gradeline at Future PWWF.....	3-7
3-6	Donahue Drive/Vomac Road Sewer – Hydraulic Gradeline at Future PWWF...	3-7
3-7	Dublin Trunk Sewer – Hydraulic Gradeline at Future PWWF.....	3-7
4-1	Proposed Sewer Improvement Projects.....	4-2
6-1	Recommended Approach for Projecting Pipeline Renewal/Replacement Timing and Cost.....	6-7