



ADWF, MGD	PF
.01	3.00
.05	2.40
.07	2.29
.08	2.25
.12	2.17
.14	2.14
.15	2.13
.16	2.12
.22	2.09
.40	2.02
.46	2.00
.57	1.96
.84	1.91

REV. 04/07

Dublin San Ramon Services District	DATE MAY 1987
PEAKING FACTOR VERSUS AVERAGE DAILY FLOW	DESIGNED DJM
SIGNED COPY ON FILE AT DISTRICT OFFICE	DRAWING S-1