

SPILL PREVENTION AND CONTROL PLAN (SPCP)

In accordance with 40 CFR Part 403.8(f)(2)(v) and the District Code, the Discharger is required to prepare a Spill Prevention and Control Plan (SPCP) in order to provide the necessary protection from **slug discharges** of restricted materials to the District's facilities. The SPCP shall contain the following information, at a minimum:

- a. A description of the discharge practices including non-routine batch discharges.
- b. A description of stored hazardous chemicals.
- c. The practices for promptly notifying the District of **slug discharges**, including any discharge that would violate a specific discharge prohibition with procedures for follow-up written notification within five (5) days.
- d. Procedures to prevent adverse impact from accidental spills including maintenance and inspection of storage areas, handling and transfer of materials, loading and unloading operations, control of plant site run-off, worker training, building or containment structures or equipment, measures for containing toxic organic pollutants (including solvents), and/or measures or equipment for emergency response.
- e. Follow-up practices to prevent additional and future damage to the District's treatment plant or the environment.
- f. A certification statement signed by an authorized representative.